




DRYVIT J-TRACK




FLANGED WINDOW



DRYVIT DRAINAGE STRIP™ OPTION



DRYVIT STARTER BOARD OPTION



NOTES:

1. DRYVIT RECOMMENDS THAT GROUND FLOOR APPLICATIONS AND ALL FACADES EXPOSED TO ABNORMAL STRESS, HIGH TRAFFIC, OR DELIBERATE IMPACT HAVE THE BASE COAT REINFORCED WITH PANZER® MESH PRIOR TO STANDARD OR STANDARD PLUS MESH. LOCATION OF HIGH IMPACT ZONES SHOULD BE INDICATED ON CONTRACT DRAWINGS.
2. REFER TO APPLICATION INSTRUCTIONS FOR THE APPROVED TREMCO CPG AIR BARRIER SYSTEM SELECTED FOR AWRB AND FLASHING APPLICATION. SEE OSL-04A THROUGH 04D INSTALLATION OPTIONS.
3. COORDINATE WITH WINDOW SHOP DRAWINGS FOR TERMINATION OF FINISH.
4. INSTALL WINDOW UNIT AND ASSOCIATED FLASHINGS PER MANUFACTURER'S RECOMMENDATIONS, CODE REQUIREMENTS AND PROJECT DOCUMENTS.
5. INSULATION BOARD TO BE MINIMUM 3/4" (19 MM).
6. WEEP TUBE DESIGN PER SPECIFICATION, AS APPLICABLE.
7. LIGHTLY SAND SURFACE OF J-TRACK TO MAXIMIZE ADHESION.
8. LENGTH OF TRACK NOT TO EXCEED 10 FT (3.0 M)

This detail is for general informational purposes only. The project design professional determines, in its sole discretion, whether this detail or a functionally equivalent detail is best suited for the project with respect to any architecture, engineering, and design requirements, including any local building code requirements. If this document is not reviewed and the product is not approved for use by a licensed design professional, the customer agrees that the detail may contain substantive flaws requiring correction, and hereby releases Tremco CPG Inc. from any and all liability related to the design and installation of the product. This detail is subject to change without notice. Contact Tremco to ensure you have the most recent version.

Outsulite™ Panel System

 <p>Dryvit Technical Support: 800-556-7752</p>	Detail: Head Drainage Options - Shop Installed Window			File Name:	 <p>OSL 10MD Construction Products Group</p>
	Drawn by: EM	Checked by: CW	Scale: NTS	OSL 10MD	
	Revision #: 0	Revised by: NA	Date: 6/27/2024		
www.tremcocpg.com					